

MOLD TESTING UNIT (MTU)

This sturdy & portable unit helps in testing of the cooling circuits of the mold after the mold manufacturing is completed and before it goes for the first trials. It is also very useful in injection Molding factories for checking the mold circuits before the mold is loaded on the machine for production. The tests that can be carried out are:

1. High pressure Leakage test.
2. Flow rate test.



FEATURES

- Tank capacity : 30 litres
(Agent : 50% water + 50% glycol).
- Electric motor pump.
- Preselection of pressure setting upto 50 bar.
 - Flow control (flow meter).
- Double filtering of the liquid with visual indication of filter conditions.
 - Dry Run Protection.



Madhu Machines & Systems Pvt. Ltd.

Registered Office:

Vadodara, India

91-9377676520

machinery@madhu-group.com

Factory:

Bengaluru, India.

91-80-28360131

mms@madhu-group.com

